

PSBXB07_33_sq-end Guidance

STANDARD DRAWING GUIDANCE (do not show on plans): (Turn off level Bridge-Guidance to hide guidance)

- ① Actual strand arrangement, bent up strands, and debonding (if any) is by design (top two strands are required). Add or remove symbols and instructions as required. Strands may be placed continuously across beam (eliminating 4" space), but dimension to drain hole in Part Plan shall be revised to 10".
- ② Revise if #5 is required. Use 8'-4° for #5-S1 actual length and 7'-9" for #5-S2 actual length.
- $\begin{tabular}{lll} \begin{tabular}{lll} \begin{$

When lap is - Delete grouped elements.
unnecessary: - Extend A bars to © Beam.
- Revise 10 to 5 A1 bars & 8 to 4 A2 bars.

 \bigoplus Interior diaphragm, void holes & vent pipe shall be shown only when necessary (when structure may be submerged).

- When not necessary: Delete the two grouped elements. In Half Elev. extend hidden lines to Q Beam. In Part Plan revise remaining dimension to full length of void.
- (5) Revise minimum dimension if required by design.
- (6) By design. Typically 30.98 kips per 0.5" strand & 43.94 kips per 0.6" strand, rounded to nearest whole kip.