

From: [Debra M. Beckwith](#)
To: [BR](#)
Subject: Bridge Advertisement (DSI 24-001) Monolithic Deck Repair after Hydro Demolition
Date: Tuesday, May 21, 2024 10:47:37 AM

The [Missouri Standard Specifications](#) have been updated as described below:

Implementation Statement: Effective for July 2024 letting.

(The Implementation Statement is a recommendation by the Development Section. The SPM is responsible for the level of implementation for any particular job.)

Revision Date	Items Revised	Description of Change
May 2024	EPG: NA	Language has been added to Sec 704.5.5 to clarify that concrete removal around reinforcement is typically not required when performing monolithic deck repair. Similar language had been present in a previous version of the JSP for hydro demolition. Language is also added to highlight that the requirements of Sec 704.5 shall be considered when performing incidental concrete removal after hydro demolition in accordance with Sec 210.110.4.4.
	Bridge Standard Drawings: NA	
	MicroStation Cells: NA	
	Std. Specifications: 704.5.5; 216.110.4.4	
	Standard Plans: NA	
	Bridge Special Provisions: NA	

Follow links above for more information, or to view more details about this (or any) revision, use the [Revision Index Database](#), located under Completed Revisions on Development’s Sharepoint page.

Instructions:

Under Tables (left-hand side) double-click on RevisionRecords.

Click on the link under the Effective Date to access documentation for the completed revision.

Debra M. (Debbie) Butchart
(formerly Debra Beckwith)
Structural Specialist
Development Section
Bridge Division
MoDOT- 105 West Capitol Ave
573-522-8718