The EPG & Bridge Standard Drawings have been updated as described below:

Implementation Statement: Effective immediately for design process not

started

(The Implementation Statement is a recommendation by the Development Section. The SPM is responsible for the level of implementation for any particular job.)

Revision Date	Items Revised	Description of Change
<u>July 2024</u>	EPG:	Chain link fence revised for LRFD specifications and
	<u>751.6, 751.12, 751.50</u>	added 120 inch straight and 96 inch curved chain link
	Bridge Standard	fence options. Fence posts are attached to top of
	Drawings:	curb. (FEN01)
	FEN01, FEN02	Chain link fence with Type D and H barrier options
	MicroStation Cells:	are also added to allow the barrier to be slip-formed
	NA	with chain link fence posts attached to back face of
	Std. Specifications:	barrier (FENO2).
	NA	
	Standard Plans:	
	NA	
	Bridge Special	
	Provisions:	
	NA	

Follow links above for more information, or to view more details about this (or any) revision, use the <u>Revision Index Database</u>, located under Completed Revisions on Development's Sharepoint page.

Instructions:

Under Tables (left-hand side) double-click on RevisionRecords.

Click on the link under the Effective Date to access documentation for the completed revision.

Debra (Debbie) Butchart

(formerly Debra Beckwith) Structural Specialist Development Section Bridge Division MoDOT- 105 West Capitol Ave 573-522-8718