

**From:** [Debra M. Butchart](#)  
**To:** [BR](#)  
**Subject:** Bridge Advertisement (DSI 24-019) Precast Panels for Bridge Decks  
**Date:** Wednesday, July 31, 2024 7:26:50 AM  
**Attachments:** [image001.png](#)

---

The [EPG](#) has been updated as described below:

**Implementation Statement:** Effective immediately for design process not started.

*(The Implementation Statement is a recommendation by the Development Section. The SPM is responsible for the level of implementation for any particular job.)*

Revision Date	Items Revised	Description of Change
<a href="#">July 2024</a>	EPG: <a href="#">751.10</a> , <a href="#">751.14</a>	Prestressed precast panels are no longer referenced as the preferred deck forming option. The choice of deck forming option (precast panels, corrugated metal forms, or transparent forms) requires approval of the Structural Project Manager, Structural Liaison Engineer, or owner's representative.
	Bridge Standard Drawings: NA	
	MicroStation Cells: NA	
	Std. Specifications: NA	
	Standard Plans: NA	
	Bridge Special Provisions: NA	

Follow links above for more information, or to view more details about this (or any) revision, use the [Revision Index Database](#), located under Completed Revisions on Development's Sharepoint page.

Instructions:

Under Tables (left-hand side) double-click on RevisionRecords.

Click on the link under the Effective Date to access documentation for the completed revision.

Debra (Debbie) Butchart

(formerly Debra Beckwith)

Structural Specialist

Development Section

Bridge Division

MoDOT- 105 West Capitol Ave

573-522-8718