

From: [Debra M. Butchart](#)
To: [BR](#)
Subject: Bridge Advertisement: Bridge Special Provisions for FRP Wrap
Date: Tuesday, August 11, 2026 7:05:54 AM

The [Bridge Special Provisions](#) have been updated as described below:

Implementation Statement: Effective immediately for projects not yet submitted to Design

(The Implementation Statement is a recommendation by the Development Section. The SPM is responsible for the level of implementation for any particular job.)

Revision Date	Items Revised	Description of Change
Aug. 2026	EPG: NA	704-BSP-06 FRP Wrap for Concrete Beams, Piles and Columns: Section 3.1 has been updated to require that the spacing of the FRP strips follow ACI 440.2R-25 requirements and to also specify the maximum gap between discrete strips.
	Bridge Standard Drawings: NA	
	MicroStation Cells: NA	
	Std. Specifications: NA	
	Standard Plans: NA	
	Bridge Special Provisions: 704	

Follow links above for more information.

Debra (Debbie) Butchart

(formerly Debra Beckwith)

Structural Specialist

Development Section

Bridge Division

MoDOT- 105 West Capitol Ave

573-522-8718